

उच्च न्यायालय मध्यप्रदेश : जबलपुर

(निविदा)

उच्च न्यायालय मध्यप्रदेश जबलपुर में सभी कोर्ट रूम्स एवं रजिस्ट्री अधिकारियों के चेम्बर्स तथा उनके शासकीय बंगलों में एवं कार्यालय के अनुभागों में स्थापित एअर कंडीशनर (नॉन इन्वर्टर, इन्वर्टर स्प्लिट एसी, 2.5 टन, 4.0 टन के कैसेट एसी, 15 टन के ब्लू स्टार पैकेज, तथा डक्टबल एसी) की सर्विसिंग एवं रखरखाव का कार्य प्रतिवर्ष किया जाता है इसके अतिरिक्त शासकीय बंगलों में एवं कार्यालय में उपयोग किये जा रहे डक्ट, विण्डो एवं डिजर्ट कूलर आदि की सर्विसिंग एवं रखरखाव का कार्य भी प्रतिवर्ष किया जाता है ।

निविदा प्रस्तुत करने हेतु इच्छुक अधिकृत फर्म एअर कंडीशनर एवं कूलर की सर्विसिंग में उपयोग आने वाली सभी प्रकार की सामग्री की दरें पृथक पृथक बंद लिफाफों में दिनांक 06.02.2025 की शाम 4:00 बजे तक प्रोटोकॉल अनुभाग में जमा करें । विस्तृत जानकारी उच्च न्यायालय मध्यप्रदेश जबलपुर की बेवसाईड **mphc.gov.in** पर देखा जा सकता है ।

सही /—

(हर्ष सिंह बहरावत)

रजिस्ट्रार(प्रशासन)

Cooler Servicing.

S. No.	Description
	Refixing of Window Cooler by Painting of Panels water tank with Primer inside and out side paint & providing wood wool in panel Chicken Mesh complete, fixing & testing & trailing.
1	Duck Cooler with 24" Exhaust Fan
2	Window Cooler with 18"x20" Exhaust/Cooler Fan.
3	Room Cooler
4	Supplying & Fixing of Duck Cooler Submercible pump with connection testing etc. as required head 8 feet.
5	Supplying & Fixing of Window Cooler Submercible pump with connection testing etc. as required head 5 feet.
6	Replacement of Speed regulator electronic 1000 watt in window cooler with testing.
7	Replacement of 12 mm thick ply in window cooler with all necessary work.
8	Replacement of Water Tank ub Duck Coller
9	Replacement of Water Tank.
10	Supplying & Fixing of Gang box.
11	Replacement of 3 core flexible round sheathed cable 40/76.
12	Replacement of 3 Pin Top 6 Amp.
13	Supplying & Fixing of Distribution Pipe.
14	Servicing by complete opening of cooler/exhaust fan motor oiling greasing testing & refitting etc.
15	Rewinding & Installing of Cooler Motor 18"x20"
16	Rewinding & Installing of Duck Cooler Motor.
17	Supplying & Fixing of Cooler Fans Blade
18	Supplying & Fixing of Stand for Window Cooler.
19	Supplying & Fixing of Flexible Pipe for Window Cooler.
20	Replacement of Exhaust Fan Bearing
21	Replacement of Exhaust Fan bearing of Duck Coller
22	Replacement of Cooler Motor Bush & Shoft
23	Supplying & Fixing of Condensor 8 Mfd.
24	Replacement of Exhaust Fan Frame and Leg Side
25	Supplying & Fixing of Exhaust Fan 600mm Sweep complete with Connection etc.
26	Supplying & Fixing of Exhaust Fan 450mm Sweep complete with Connection etc.
27	Supplying & Fixing of 20" Cooler Fan Motor in Room Coller.
28	Supplying & Fixing of 12" High Speed Cooler Motor in Room Cooler
29	Replacement of Old Rusted & Un-repairable Side or back panel of window coolers size of panels may vary between 24"x42" to 30"x42" including angle iron frame of 25x3mm and square mesh etc. complete but without wood wool filling etc.
30	Supplying & Fixing of Grill in Cooler.
31	Complete Duck Cooler all Item shifting of labour charge.
32	Complete Window Cooler shifting of labour charge.
33	Supplying & Fixing of Duck Cooler Exhaust Fan Blade

Subject: Servicing and repairing of Split multi split and Windows type air Conditioner.

S.No.	Particular
1	Chemical jet power Servicing of Multi Split Air – Conditioner
2	Chemical jet power Servicing of Split type Air – Conditioner
3	Chemical jet power Servicing of Window type Air – Conditioner
4	Installation of Multi Split type Air - Conditioner
5	Installation of Split type Air – Conditioner
6	Installation of Window type Air – Conditioners without grill cutting Wall open and carpenter wooden work
7	Nitrogen leak testing repairing by breezing and then refrigerant R-22 charging in 1 nos circuit of multi split AC, split AC and Window AC
8	Refrigerant R-22 charging in split AC, multi AC and Window AC
9	Dismantling of Multi Split AC, both indoor and outdoor with copper tube and loading the gas pressure back in outdoor unit etc.
10	Dismantling of Multi Split AC, both indoor and outdoor with copper tube and load in the gas pressure back in outdoor unit etc.
11	Dismantling of Window type Air – Conditioner
12	Providing and fixing of compressor 1.5 Ton Split & Window LG make refitting of compressor with breezing of copper tube.

	Providing and fixing of capacitor 50+60 MFD in Multi Split , Split and Window type Air – Conditioner
14	Gas Top up refrigerant R-22 in 1 Nos Circuit of Multi Split, Split and Window type Air – Conditioner
15	Providing and fixing of contract MNXA 1 in Multi Split, Split Air - Conditioner
16	Providing and fixing of contractor TCDP 401 in VOLTAS make Split type Air - Conditioner
17	Providing and fixing of relay selector Switch Swing Motor thimble pin short repairing
18	Providing and fixing of fan motor LC make Window type AC
19	Providing and fixing of fan motor LG make in Split, Multi Split Air - Conditioner
20	Providing and fixing PCB in Split and Multi Split AC
21	Providing and fixing PCB in Window type AC
22	Copper tube with installation and Wiring 5/8 and ½ running per feet
23	Copper tube with installation and wiring ½ and ¾ running Air – Conditioner
24	Fan motor rewinding by copper wiring with refitting in Air – Conditioner
25	Providing and fixing Display PCB of Split and Multi Split AC with refitting Indoor unit
26	Supplying of LG make remote control of Air – Conditioner
27	Rectification of minor complaints like drain trouble low cooling, wiring short, Power supply trouble, remote function etc.

28	Re-servicing of Multi Split, Split and Window type AC
29	Providing and fixing of Condenser coil with Nitrogen leak testing and then refrigerant R-22 charging in Split, Window AC
30	Providing and fixing of indoor blower fan
31	Providing and fixing of outdoor fan blade
32	Providing and fixing of remote inverter A.C.
33	Refitting of compressor nitrogen pressure testing brising in copper piping
34	Providing and fixing of compressor refrigerant 410 and R-32 make
35	Providing and fixing of shall in the remote of Air – Conditioner each AC
36	Providing and fixing of Drain pipe per meter
37	Providing and fixing of MS stand for install outdoor unit
38	Providing and fixing of Copper Wire 4 core 2.5 sqmm per meter
39	Providing and fixing of elankey wall suction and discharge
40	Providing and fixing of 16 Amp 3 pin plug

Sr.No.	Description	Qty
	Godrej Inverter Split Ac 2.0 Ton Indoor Unit	
1	Inverter Indoor PCB	01 Nos
2	Fan Motor	01 Nos
3	Fan Blower	01 Nos
4	Indoor Sensor	01 Nos
5	Indoor Display	01 Nos
6	Drain Pipe	Per mtr
7	Remote Control	01 Nos
8	Swing Motor	01 Nos
	Godrej Inverter Split Ac 2.0 Ton Outdoor Unit	
1	Inverter Compressor	01 Nos
2	Outdoor Inverter PCB	01 Nos
3	Fan Motor	01 Nos
4	Fan Blade	01 Nos
5	Outdoor Sensor	01 Nos
6	Suction & Discharge Valve	01 Nos
7	Cooper pipe	Per Feet
8	Gas Charging & Presser Testing	01 Nos
9	Gas Top-Up	01 Nos
10	Ac Installation	01 Nos
11	Ac Dismantle	01 Nos
12	Compressor Fitting & Presser Testing	01 Nos
13	Split Ac Servicing	01 Nos
14	Service Charge	01 Nos
15	2.5 mm cable 4 core	Per mtr
16	3 Pin Top	01 Nos

Sr.No.	Description	Qty
	Voltas Inverter split Ac 1.5 Ton Indoor Unit	
1	Inverter Indoor PCB	01 Nos
2	Fan Motor	01 Nos
3	Fan Blower	01 Nos
4	Indoor Sensor	01 Nos
5	Indoor Display	01 Nos
6	Drain Pipe	Per mtr
7	Remote Control	01 Nos
8	Swing Motor	01 Nos
	Voltas Inverter split Ac 1.5 Ton Outdoor Unit	
1	Inverter Compressor	01 Nos
2	Outdoor Inverter PCB	01 Nos
3	Fan Motor	01 Nos
4	Fan Blade	01 Nos
5	Outdoor Sensor	01 Nos
6	Suction & Discharge Valve	01 Nos
7	Gas Charging & Presser Testing	01 Nos
8	Gas Top-Up	01 Nos
9	Ac Installation	01 Nos
10	Ac Dismantle	01 Nos
11	Cooper pipe	Per Feet
12	Compressor Fitting & Presser Testing	01 Nos
13	Split Ac Servicing	01 Nos
14	Service Charge	01 Nos
15	2.5 mm cable 4 core	Per mtr
16	3 Pin top	01 Nos

Sr.No.	Description	Qty
	L.G. Cassette Inverter Ac Hot & Cool 4 Ton Indoor Unit (CJ Court) – 1 No	
1	Inverter Indoor PCB	01 Nos
2	Fan Motor	01 Nos
3	Fan Blower	01 Nos
4	Indoor Sensor	01 Nos
5	Indoor Display	01 Nos
6	Drain Pipe	Per mtr
7	Remote Control	01 Nos
8	Swing Motor	01 Nos
9	Drain Pump	01 Nos
10	Drain Pump Sensor	01 Nos
	L.G. Inverter Cassette Ac Hot & Cool 4 Ton Outdoor Unit CJ Court – 1 No	
1	Inverter Compressor	01 Nos
2	Outdoor Inverter PCB	01 Nos
3	Outdoor Inverter Filter PCB	01 Nos
4	Outdoor Main PCB	01 Nos
5	Fan Motor	01 Nos
6	Fan Blade	01 Nos
7	Outdoor Sensor	01 Nos
8	Suction & Discharge Valve	01 Nos
9	Gas Charging & Presser Testing	01 Nos
10	Gas Top-Up	01 Nos
11	Ac Installation	01 Nos
12	Ac Dismantle	01 Nos
13	Cooper pipe	Per Feet
14	Compressor Fitting & Presser Testing	01 Nos
15	Cassette Ac Servicing	01 Nos
16	Service Charge	01 Nos
17	4 mm cable 4 core	Per mtr
18	3 Pin Top	01 Nos

Sr.No.	Description	Qty
	L.G. Cassette Inverter Ac Hot & Cool 2.5 Ton Indoor Unit (CJ Court) – 1 No	
1	Inverter Indoor PCB	01 Nos
2	Fan Motor	01 Nos
3	Fan Blower	01 Nos
4	Indoor Sensor	01 Nos
5	Indoor Display	01 Nos
6	Drain Pipe	Per mtr
7	Remote Control	01 Nos
8	Swing Motor	01 Nos
9	Drain Pump	01 Nos
10	Drain Pump Sensor	01 Nos
	L.G. Inverter Cassette Ac Hot & Cool 2.5 Ton Outdoor Unit CJ Court – 1 No	
1	Inverter Compressor	01 Nos
2	Outdoor Inverter PCB	01 Nos
3	Outdoor Inverter Filter PCB	01 Nos
5	Fan Motor	01 Nos
6	Fan Blade	01 Nos
7	Outdoor Sensor	01 Nos
8	Suction & Discharge Valve	01 Nos
9	Gas Charging & Presser Testing	01 Nos
10	Gas Top-Up	01 Nos
11	Ac Installation	01 Nos
12	Ac Dismantle	01 Nos
13	Cooper pipe	Per Feet
14	Compressor Fitting & Presser Testing	01 Nos
15	Cassette Ac Servicing	01 Nos
16	Service Charge	01 Nos
17	4 mm cable 4 core	Per mtr
18	3 Pin Top	01 Nos

Sr.No.	Description	Qty
	L.G. Cassette Inverter Ac 4 Ton Indoor Unit	
1	Inverter Indoor PCB	01 Nos
2	Fan Motor	01 Nos
3	Fan Blower	01 Nos
4	Indoor Sensor	01 Nos
5	Indoor Display	01 Nos
6	Drain Pipe	Per mtr
7	Remote Control	01 Nos
8	Swing Motor	01 Nos
9	Drain Pump	01 Nos
10	Drain Pump Sensor	01 Nos
	L.G. Inverter Cassette Ac 4 Ton Outdoor Unit	
1	Inverter Compressor	01 Nos
2	Outdoor Inverter PCB	01 Nos
3	Outdoor Main PCB	01 Nos
4	Fan Motor	01 Nos
5	Fan Blade	01 Nos
6	Outdoor Sensor	01 Nos
7	Suction & Discharge Valve	01 Nos
8	Gas Charging & Presser Testing	01 Nos
9	Gas Top-Up	01 Nos
10	Ac Installation	01 Nos
11	Ac Dismantle	01 Nos
12	Cooper pipe	Per Feet
13	Compressor Fitting & Presser Testing	01 Nos
13	Cassette Ac Servicing	01 Nos
14	Service Charge	01 Nos
15	4 mm cable 4 core	Per mtr
16	3 Pin Top	01 Nos

Sr.No.	Description	Qty
	Voltas Cassette Non Inverter Ac 4 Ton Indoor Unit	
1	Indoor PCB	01 Nos
2	Fan Motor	01 Nos
3	Fan Blower	01 Nos
4	Indoor Sensor	01 Nos
5	Indoor Display	01 Nos
6	Drain Pipe	Per mtr
7	Remote Control	01 Nos
8	Swing Motor	01 Nos
9	Drain Pump	01 Nos
10	Drain Pump Sensor	01 Nos
	Voltas Cassette Non Inverter Ac 4 Ton Outdoor Unit	
1	Compressor	01 Nos
2	Capacitor	01 Nos
3	Contactora	01 Nos
4	Fan Motor	01 Nos
5	Fan Blade	01 Nos
7	Suction & Discharge Valve	01 Nos
8	Gas Charging & Presser Testing	01 Nos
9	Gas Top-Up	01 Nos
10	Ac Installation	01 Nos
11	Ac Dismantle	01 Nos
12	Cooper pipe	Per Feet
13	Compressor Fitting & Presser Testing	01 Nos
14	Cassette Ac Servicing	01 Nos
15	Service Charge	01 Nos
16	4 mm cable 4 core	Per mtr
17	3 Pin Top	01 Nos

Sr.No.	Description	Qty
	Library (5TR Blue Star Ductable Ac) Indoor Unit	
1	Blower Motor	01 Nos
2	Blower	01 Nos
3	Coil Sensor	01 Nos
4	Room Sensor	01 Nos
5	Blower Motor Rewinding	01 Nos
6	Fan Capacitor	01 Nos
7	PCB Board	01 Nos
8	Remote Control	01 Nos
	Library (5TR Blue Star Ductable Ac) Outdoor Unit	
1	5 TR Compressor (ZR72)	01 Nos
2	Contactor 3 Phase 63Amp	01 Nos
3	Single Phase Preventer	01 Nos
4	Connector	01 Nos
5	HP/LP Switch	01 Nos
7	Condenser Fan Motor	01 Nos
8	Fan Blade	01 Nos
9	Dryer Filter	01 Nos
10	Gas Charging & Presser Testing	01 Nos
11	Compressor Fitting & Presser Testing	01 Nos
12	Service Charge	Per Feet
13	Servicing	01 Nos

	Package Unit Control Panel	Qty
1	3 Phase Contactor	01 Nos
2	Overload	01 Nos
3	Relay CR	01 Nos
4	Big Connector	01 Nos
5	Small Connector	01 Nos
6	Fuse	01 Nos
7	Selector Switch	01 Nos
8	Restart Switch	01 Nos
9	Indicator HP/LP Lamp	01 Nos
	Main Control Electrical Panel	Qty
1	FN Switch 63 Amp	01 Nos
2	Ampere Meter	01 Nos
3	Volt Meter	01 Nos
4	Main Switch 200 Amp Meter	01 Nos
5	Connector 63 Amp	01 Nos
6	On/Off Switch	01 Nos
7	(Up Down) Small On/Off Switch	01 Nos
8	R.Y.B. Switch	01 Nos
9	RYB Indicator Lamp	01 Nos

Sr.No.	Description	Qty
	Blue Star Package Ac Plant 15 Ton Indoor Unit	
2	Compressor CRN5	01 Nos
3	Expansion Valve	01 Nos
4	Fan Blower Motor	01 Nos
5	Blower Motor Belt	01 Nos
6	HP / LP Switch	01 Nos
7	Suction Discharge Valve	01 Nos
8	Dryer Filter	Per mtr
9	Thermostat	01 Nos
10	Hand Sutter Wall	01 Nos
11	Fan Blower	01 Nos
12	Blower Shaft Baring	01 Nos
13	Fan Blower Shaft	01 Nos
14	Heater Element Road	01 Nos
15	Return Air Exhaust Fan	01 Nos
16	Duct Canvas	01 Nos
17	10/4 Aluminum Main Cable 4 Core	Per Mtr
18	4mm 4 Core Copper Wire	Per Mtr
	Blue Star Package Ac Plant 15 Ton Outdoor Unit Cooling Tower	
1	Condensing Fan Motor	01 Nos
2	Flout Wolves	01 Nos
	Condensing Fan Motor re winding	01 Nos
3	Pump Motor 10 HP	01 Nos
4	Gauge Meter	01 Nos
5	Servicing	01 Nos
6	Gas Charging & Presser Testing	01 Nos
7	Gas Top-Up	01 Nos
8	Compressor Fitting & Presser Testing	01 Nos
9	Service Charge	01 Job

Sr.No.	Description	Qty
	Library (11TR Blue Star Ductable Ac) Indoor Unit	
1	Blower Motor	01 Nos
2	Blower	01 Nos
3	Coil Sensor	01 Nos
4	Room Sensor	01 Nos
5	Blower Motor Rewinding	01 Nos
6	Fan Capacitor	01 Nos
7	PCB Board	01 Nos
8	Remote Control	01 Nos
	Library (11TR Blue Star Ductable Ac) Outdoor Unit	
1	5 TR Compressor (ZR72)	01 Nos
2	Contactor 3 Phase 63Amp	01 Nos
3	Single Phase Preventer	01 Nos
4	Connector	01 Nos
5	HP/LP Switch	01 Nos
7	Condenser Fan Motor	01 Nos
8	Fan Blade	01 Nos
9	Dryer Filter	01 Nos
10	Gas Charging & Presser Testing	01 Nos
11	Compressor Fitting & Presser Testing	01 Nos
12	Service Charge	Per Feet
13	Servicing	01 Nos

Note- GST@18% Extra