

उच्च न्यायालय मध्यप्रदेश : जबलपुर

उच्च न्यायालय मध्यप्रदेश जबलपुर में संस्थापित 85 नग स्प्लिट एअर कंडीशनर, 05 नग मल्टी स्प्लिट एसी तथा 14 नग विण्डो एसी कुल 104 एअर कंडीशनर का प्रतिवर्षानुसार सर्विसिंग का कार्य संपादित किया जाना है । इच्छुक फर्म कार्यालय के प्रोटोकॉल अनुभाग में बंद लिफाफे में कोटेशन दिनांक 08/04/2019 दिन सोमवार प्रातः 11:00 बजे तक अनिवार्य रूप से जमा कर सकते हैं । सर्विसिंग हेतु विस्तृत जानकारी म0प्र0 उच्च न्यायालय के बेबसाईट [www.mphc.gov.in](http://www.mphc.gov.in) पर उपलब्ध है ।

सही/-  
(सतीश चन्द्र राय )  
रजिस्ट्रार(प्रशासन)

A.C. सर्विसिंग हेतु वेबसाइट में अपलोड करने बाबत ।

|     |   |
|-----|---|
| 1.  | Chemical Servicing of Multi Split Air-conditions  |
| 2.  | Chemical Servicing of Split type Air-conditions   |
| 3.  | Chemical Servicing of window type Air-conditions  |
| 4.  | Installation of multi split type Air-conditions   |
| 5.  | Installation of split type Air-conditions   |
| 6.  | Installation of window type Air-conditions without grill cutting wall open & carpenter wooden work  |
| 7.  | Nitrogen leak testing repairing by breezing and then refrigerant R-22 charging in 1 nos. circuit of Multi split AC Split AC & window AC   |
| 8.  | Refrigerant R-22 charging in split AC, Multi AC & window AC   |
| 9.  | Dismantling of Multi Split AC, both Indoor & Outdoor with copper tube and loading the gas pressure back in outdoor unit etc.  |
| 10. | Dismantling of split AC both Indoor & Outdoor with copper tube and loading the gas pressure back in outdoor unit etc.   |
| 11. | Dismantling of window type Air- conditioner   |
| 12. | Providing and fixing of compressor 1.5 Ton, Split & window LG make refitting of compressor with breezing of copper tube, suction and discharge after Nitrogen leak testing refrigerant R-22 charging. |

|     |  |
|-----|--|
| 13. | Providing and fixing of capacitor 50+6 MFD in multi split, split and window type Air conditioner                           |
| 14. | Gas Topup refrigerant R-22 in 1 Nos. Circuit of multi split, split and window type Air conditioner                         |
| 15. | Providing and fixing of contractor MNXA 1 in multi split, split Air conditioner  |
| 16. | Providing and fixing of contractor TCDP 401 in VOLTAS make split type Air conditioner                                      |
| 17. | Providing and fixing of relay selector switch swing motor thimble pin short repairing.                                     |
| 18. | Providing & fixing of fan motor LG make window type AC.  |
| 19. | Providing & fixing of fan motor LG make in split, multi split Air conditioner  |
| 20. | Providing & fixing P.C.B. in split & multi split AC  |
| 21. | Providing and fixing of P.C.B. in window type AC   |
| 22. | Copper tube with installation and wiring 5/8 and 1/4 running per feet.   |
| 23. | Copper tube with Installation and wiring 1/2 and 3/4 running per feet.   |
| 24. | Fan motor rewinding by copper wiring with refitting in Air conditioner.  |
| 25. | Providing & fixing of Display PCB of split and multi split AC with refitting Indoor unit.                                  |
| 26. | Supplying of LG make remote control of Air conditioner.  |
| 27. | Rectification of minor complaints like drain trouble, low cooling, wiring shot, power supply trouble, remote function etc. |
| 28. | Re-servicing of multi split, split and window type AC.   |
| 29. | Providing and fixing of condenser coil with Nitrogen leak testing and then refrigerant R-22 charging in split, window AC.  |